BANGALORE CITY MUNICIPALITY.

Notice No. 705, *dated* 8—12*th September* 1910

Notice is hereby given that sealed tenders will be received by the President, City Municipal Council, Bangalore, for constructing a Masjid, a cistern, watchman-shed, compound wall and providing water connection in the Mahomedan Burial ground on Mysore road, Bangalore City, up to 30th September 1910.

2. Plans and detailed estimate can be seen in the Municipal Engineer's Office during office hours.

3. The approximate quantities and items of works to be carried out are given below.

4. Each tenderer must definitely state the rate at which he would carry out each item. The work must be completed by the end of February 1911.

5. Tenders must be accompanied by a deposit of Rs. 300 (in cash or currency notes) as earnest money and be superscribed "Tender for constructing Masjid, etc., in Mahomedan Burial ground, Bangalore City."

6. The final acceptance of the tender rests with the Deputy Commissioner, Bangalore District, who does not bind himself to accept the lowest or any tender.

7. The name of the successful tenderer, whose tender has been accepted, will be posted on the notice board in the Municipal Engineer's Office in due course.

No enquiries regarding the acceptance or rejection of a tender will receive any attention.

8. The successful tenderer will be required to execute a bond within a week after the acceptance of his tender. In default, the tenderer will forfeit his earnest money and his contract will be considered null and void.

9. The earnest money of rejected tenderers will be returned to them on the above or any subsequent date by the President, City Municipal Council, Bangalore.

Items of work	*Per*	*Quantity*
Earthwork, excavation	C. yd.	83
Burnt stone in clay	C. ft.	2,208
Burnt brick in clay	"	4,041
Brick in chunam	"	329
Stone slabs, 4" thick	S. ft.	532
Chunam plastering	Sq.	62·39
Whitewashing, 2 coats	"	39·73
Colour-washing	"	37·17
Teakwood work	C. ft.	244·34
Stone pillars 9"×9"×7½' with bases, caps and neatly dressed	No.	6
Zinc valley gutters with teak planks	S. ft.	132
Roofing with first class Mangalore tiles	Sq.	32·57
Ornamental ridge tiles	R. ft.	72
Iron trusses for 20' span	No.	4
Teakwood ornamental eave-board	R. ft.	262
Gable finials	No.	4
Valley finials	No.	4
Flooring with Cuddapah slabs over sand bed	Sq.	4·24
Flooring with Mangalore tiles	"	8·00
Teakwood panelled doors	S. ft.	74
Teakwood swing fan lights	"	61
Teakwood venetianed and glazed windows	"	176
Teakwood glazed swing ventilators	"	96
Teakwood gabled windows with coloured glasses	"	36
Chunam pointing for basement	Sq.	5 32
Painting doors, windows, etc.	"	8·35
Wood-oiling	"	24·57
Earth-filling	C. yd.	132
Filling concrete foundation	C. ft.	246
Burnt brick in chunam with surki	"	414
Constructing drain at the top of well	R. ft.	69
Stone blocks well dressed for foot rests	No.	35
Cement plastering	Sq.	7·28
Cuddapah slab flooring over 3" concrete	"	4·55
Mud plastering	"	14·37
Eave-board, ordinary	R. ft.	120
Teakwood battened doors	S. ft.	36
Teakwood windows, complete	"	45
Teakwood finials	No.	2
Constructing a compound wall with end pillars and ornamentation, etc., complete	R. ft.	620
Teakwood gates with double shutters and iron vertical bars ¾" diameter with latches, etc., complete	S. ft.	140
Providing water-connections with outlet drain, etc.	Lump sum.	

N. SUBBA RAO,
For *President.*